

**CITY OF TROUTDALE  
CONSTRUCTION DETAILS  
INTERIM CHANGES**

**TABLE OF CONTENTS**

**IC 1 – Sanitary Sewer Manhole Locations, Spacing, Inverts..... tab 1**  
**IC 2 – Number of Water Service Meters per Property ..... tab 2**  
**IC 3 – RECINDED ..... tab 3**  
**IC 4 – Add New Drawing II-29 – Town Center Overlay Street .tab 4**  
**IC 5 – RECINDED ..... tab 5**  
**IC 6 – Gravel Construction Entrance Rock..... tab 6**  
**IC 7 – Superseded by IC #'s 26 and 27 ..... tab 7**  
**IC 8 – Access Management for Driveways..... tab 8**  
**IC 9 – Superseded by IC #10..... tab 9**  
**IC 10 – Superseded by IC #19..... tab 10**  
**IC 11 – Catch Basins Filter Bags, Biobags ..... tab 11**  
**IC 12 – Fire Hydrants ..... tab 12**  
**IC 13 – Certification of Buildable Lots..... tab 13**  
**IC 14 – Meter Makes/Models Deleted..... tab 14**  
**IC 15 – Storm Sewer Design ..... tab 15**  
**IC 16 – Storm Sewer Collection – Rainfall Intensities..... tab 16**  
**IC 17 – Drawing II-1 Updated - C/I Street Cross Section ..... tab 17**  
**IC 18 – Drawing VIII-3 Replaced - Manhole Base ..... tab 18**  
**IC 19 – Superseded by IC #30..... tab 19**  
**IC 20 – Fire Hydrant Drawings Replaced..... tab 20**  
**IC 21 – Vertical Datum and As-Built Survey Requirements .... tab 21**  
**IC 22 – OHA-DWP Plan Review Exemption – Water Mains... tab 22**  
**IC 23 – ODEQ Exemption – Gravity Sanitary Sewer ..... tab 23**  
**IC 24 – Sidewalk Ramp Drawings Replaced ..... tab 24**  
**IC 25 – Stormwater Quality Treatment (PSWMM)..... tab 25**  
**IC 26 – Acceptable Water Meters ..... tab 26**  
**IC 27 – Acceptable Water Meter Boxes..... tab 27**  
**IC 28 – Clustered Mailboxes ..... tab 28**  
**IC 29 – Sidewalk Cutting/Grinding ..... tab 29**  
**IC 30 – Driveway Drawings Replaced, Driveway Locations .... tab 30**  
**IC 31 – Drawing Replaced – 14’ Wide Speed Hump ..... tab 31**

**IC 32 - Meter Box Specifications for ¾ & 1" Service Laterals....tab 32**  
**IC 33 - Driveway & Sidewalk Concrete & Rock Standards.....tab 33**  
**IC 34 - Erosion Control Standards.....tab 34**  
**IC 35 - Stormwater Quality Treatment Requirements.....tab 35**  
**IC 36 -**

**CITY OF TROUTDALE  
CONSTRUCTION DETAILS**

**TABLE OF CONTENTS**

**PART I - STREETS**

Streets (General Requirements) ..... I - 1  
Standards for Pavement Overlays ..... I - 4

**PART II - STREETS (Construction Details)**

Commercial/Industrial Street (cross section) .....II - 1  
Neighborhood Collector (cross section)..... II - 2  
Local Street (cross section) ..... II - 3  
Cul-de-sac & Intersection Radii..... II - 4  
Curbs & Weepholes ..... II - 5  
Straight Curb ..... II - 6  
Curb Knock-out for Driveways ..... II - 7  
Concrete Cross Gutters ..... II - 8  
Wheel Chair Ramps ..... II - 9  
Concrete Sidewalk ..... II -10  
Driveway Approach (Single Family Residential) .....II - 11  
Driveway Approach (Multi-Family Residential,  
Commercial/Industrial).....II - 12  
Utility Easement Access Way .....II - 13  
Street Cut & Repairs .....II - 14  
Street Light Pole Location (back of walk) .....II - 15  
Street Light Pole Location (in landscaping strip) .....II - 16  
Mail Box Installations (cluster & single).....II - 17  
Survey Monument & Box .....II - 18  
Street Barricade (Type II) .....II - 19  
Street Barricade (Types I & III) .....II - 20  
Public/Private Utility Locations .....II - 21  
Bomanite Pedestrian Crosswalk .....II - 22  
Neighborhood Watch Signs .....II - 23

Private Street Sign.....	II - 24
14' Wide Speed Hump .....	II - 25
Gravel Construction Entrance .....	II - 26
Not a Permanent Dead-End Street Sign .....	II - 27
In-Concrete Sidewalk Street Sign Sleeve Detail.....	II - 28

**PART III - WATER DISTRIBUTION SYSTEM**

Water Distribution System (General Requirements).....	III - 1
---	---------

**PART IV - WATER DISTRIBUTION SYSTEM (Construction Details)**

Thrust Blocks.....	IV - 1
Fire Hydrant Assembly (Behind Sidewalk).....	IV - 2
Fire Hydrant Assembly (Behind Curb).....	IV - 3
Valve Box & Operator Extension Assembly .....	IV - 4
Air Release Valve Assembly .....	IV - 5
Air & Vacuum Release Valve Assembly .....	IV - 6
Water Sampling Station .....	IV - 7
1" Double Water Service.....	IV - 8
3/4" to 2" Single Water Service.....	IV - 9
In Cul-de-sac Double/Single Service Configuration.....	IV - 10
In Half Cul-de-sac Double/Single Service Configuration.....	IV - 11
3" Diameter (and larger) Water Meter Vault.....	IV - 12
Meter with Remote Reader & Vault.....	IV - 13
Water Meter with Bypass Detail .....	IV - 14
Pressure Regulating Vault .....	IV - 15
Double Check Backflow Preventor Device Vault .....	IV - 16
Dead-end Blowoff Assembly .....	IV - 17
In-line Blowoff Assembly .....	IV - 18

**PART V - STORM SEWER COLLECTION SYSTEM**

Storm Sewer Collection System (General Requirements) .....	V - 1
---	-------

**PART VI - STORM SEWER COLLECTION SYSTEM**  
**(Construction Details)**

**Catch Basin ..... VI - 1**  
**Ditch Inlet..... VI - 2**  
**Flat Area Inlet (Unimproved Surfaces Only)..... VI - 3**  
**Flat Top Manhole (Storm Only) ..... VI - 4**  
**Large Concrete Storm Manhole Bases..... VI - 5**  
**Drywell Detail ..... VI - 6**  
**Storm Sewer Lateral & Marker (Shallow Trench) ..... VI - 7**  
**Storm Sewer Lateral (Deep Trench) ..... VI - 8**  
**Storm Manhole (48" Diameter) ..... VI - 9**  
**Permitted Drywell Construction Area ..... VI - 10**

**PART VII - SANITARY SEWER COLLECTION SYSTEM**

**Sanitary Sewer Collection System**  
**(General Requirements)..... VII - 1**

**PART VIII - SANITARY SEWER COLLECTION SYSTEM**  
**(Construction Details)**

**Sanitary Manhole (48" Diameter) ..... VIII - 1**  
**Manhole Lids & Frames (Sanitary & Storm) ..... VIII - 2**  
**48" Manhole Base (Sanitary or Storm)..... VIII - 3**  
**Trench Backfill, Bedding & Pipe Zone ..... VIII - 4**  
**Inside Drop Connection for Manholes (San. or Storm)..... VIII - 5**  
**Outside Drop Connection for Manholes (San. or Storm)..... VIII - 6**  
**Cleanout..... VIII - 7**  
**Sanitary & Storm Manholes & Cleanouts Marker Post ..... VIII - 8**  
**Sanitary Sewer Lateral & Marker (Shallow Trench) ..... VIII - 9**  
**Sanitary Sewer Lateral (Deep Trench) ..... VIII - 10**  
**Manhole Ring Adjustments (Sanitary & Storm)..... VIII - 11**  
**Cam-Lock Manhole Cover & Frame**  
**(Cast Iron & Aluminum)..... VIII - 12**  
**Bore Casing Detail..... VIII - 13**  
**Concrete Cradle & Cap Detail ..... VIII - 14**

Pipe Anchor Detail .....	VIII - 15
Concrete Apron Detail.....	VIII - 16

**PART IX - EROSION CONTROL MEASURES**

Erosion Control Measures (General Requirements) .....	IX - 1
--	--------

**PART X - EROSION CONTROL MEASURES**

**(Construction Details)**

Temporary Sediment Fence.....	X - 1
Temporary Straw Bale Silt Barrier .....	X - 2
Biofilter Bags in Ditches & Swales.....	X - 3
Biofilter Bag for Overland Water Flow (Option 1) .....	X - 4
Biofilter Bag for Overland Water Flow (Option 2) .....	X - 5
Biofilter Bag - Protected Catch Basin Detail .....	X - 6
Temporary Site Interceptor (Swales & Dikes).....	X - 7
Erosion Control for Single Lots .....	X - 8
Filter Bag Inlet Detail .....	X - 9
Sediment Trap .....	X - 10
Sediment Pond .....	X - 11
Erosion Control Blanket Installation Detail.....	X - 12
Continuous Geosynthetic Berm.....	X - 13

**PART XI - GARBAGE & RECYCLING CONTAINER ENCLOSURES**

Garbage & Recycling Container Enclosures (General Requirements) .....	XI - 1
--	--------

**PART XII - GARBAGE & RECYCLING CONTAINER ENCLOSURES**

**Garbage & Recycling Container Enclosures  
(Construction Details)**

Multi-Family Sample 1 .....	XII - 1
Multi-Family Sample 2.....	XII - 2

**Multi-Family Sample 3.....XII - 3**  
**Commercial Sample 1.....XII - 4**  
**Commercial Sample 2.....XII - 5**  
**Commercial Sample 3.....XII - 6**  
**Commercial Sample 4.....XII - 7**  
**Commercial Sample 5.....XII - 8**  
**Commercial Sample 6.....XII - 9**

